

## Park Amenities for the North Shore Overlook & Trailhead

- 1.01 SCOPE OF WORK: Provide all labor, materials, equipment, fuel and other incidental costs and supervision necessary for the furnishing and delivery of Park Amenities at North Shore Overlook & Trailhead.

### Misc. Items to be noted:

- 10- Kirby Built benches (Hampton brand) – **CEDAR/BLACK**. Dimensions: 75" Long X 24" Wide X 32" Height ( 18" high seat )
- 2- Kirby Built bike racks (Standard brand **ABK 1000**) – **BLACK**- Single sided, 3 Bike. Dimensions: 35" Long X 21" Wide x 30"High, Weight 29 lbs.
- 6- Kirby Built trash cans (Olympia brand) – **BLACK**- 32 Gallon receptacle. Dimensions: 29" Diameter X 36" Height, Weight 48 lbs.
- 3- Polly Products- Hexagon Picnic Tables 40" Recycled Plastic Attached Benches (Portable) - **BLACK** top, **BLACK** base. Dimensions: 40" Long X 46.2" Wide X 17" Height, Weight 267 lbs.
- 1- Polly Products- ADA Wheelchair Accessible Hexagon Picnic Table 40" Recycled Plastic attached Benches (Portable) - **BLACK** top. **BLACK** base. Dimensions: 40" Long X 45.25" Wide X 17.5" Height, Weight 235 lbs.
- 2- Park A Bike Public Bike Pumps- **BLACK**. Dimensions: 9.5" Wide X 27.5" Height (see attached spec sheet)
- 1 Halsey Taylor cast Iron Drinking Fountain- **BLACK**. 14" Wide X 36" Height, ( see attached spec sheet )
- See attached photos spec sheets for verification
- **NO SUBSTITUTIONS PERMITTED**
- Must contact Gallus Quigley (352-516-8512) 24 hours in advance prior to delivery
- **Price includes delivery and off load to North Shore Overlook & Trailhead- 20700 CR# 455 Ferndale FL, 34715**
- **Park Amenities must be delivered Tuesday through Friday 8:00AM through 3:00PM**
- **All amenities to be delivered within 20 days of issuance of purchase order.**





## Hampton

- Sweeping curve designed for comfort
- Recycled plastic lumber boards
- Powder-coated cast aluminum frame
- Suitable for indoor or outdoor seating
- Easy surface mounting predrilled holes
- Add a bronze plaque to your bench, see pg. 79




**IN STOCK**  
QUICK  
DELIVERY

75" l x 24" w x 32" h  
18" h seat  
120 lbs.



## Standard

- 100% recycled plastic lumber
- Single or double-sided available
- Accommodate up to 10 bikes
- Won't scratch or mar bikes
- Will not chip, rust or need paint
- Stainless steel assembly hardware included



ABK1010



*Single-Sided, 3 Bike*  
35" l x 21" w x 30" h  
29 lbs.




ATR2200

Patent Pending




## Olympia

- Attractive, weather-resistant, recycled plastic lumber
- 32-gallon capacity receptacle's flat lid & liner included
- Looks great in any location
- Stainless steel hardware
- No rotting, splintering or breaking
- No assembly required







PPASMOHT02

Hexagon Picnic Table 40 Inch  
Recycled Plastic Attached Benches,  
Portable

Manufacturer: Polly Products

[Print](#)

[Email](#)

[More...](#)

**BLACK TOP BLACK BASE**


This open seat hexagon table is handcrafted for easy assembly. The tops are assembled saving you time and money. The seating on our hex tables accommodate all ages. The easy slide in access seating allows for ease of use. They are perfect for office areas there is no stepping over a seat on this table. The 100% recycled plastic lumber construction is assembled with a heavy duty frame of solid 4x4 and 2x4 lumber and all held together using stainless steel fasteners making it durable and maintenance-free. It will not rust, or need paint. The recycled plastic lumber with rich, bold colors molded-in is available for this product in our full spectrum of offered colors which make them a complimentary and attractive application perfect for schools, libraries, churches, parks and local community centers. This item is shipped partially assembled with full instructions for the minimal assembly required to finish the structure using standard hand tools. Our optional anchor kit is available to securely affix the unit in place to aid as a theft deterrent.

#### Product Specifications

#### Product reviews

#### Product tags

Weight:	267 lbs
Height:	17.5 in
Length:	40 in
Width:	46.2 in
Picnic Table Type	Picnic Table
Construction	Recycled Plastic
Table Shape	Hexagonal
Mounting Method	Portable
Assembly Required	Yes



PPASMOHTHA02

ADA Wheelchair Accessible Hexagon  
Picnic Table 40 Inch Recycled Plastic  
Attached Benches, Portable

Manufacturer: **Polly Products**

[Print](#)

[Email](#)

[More...](#)


**BLACK TOP BLACK BASE**

This wheelchair accessible hexagon table is handcrafted for easy assembly. The tops are assembled saving you time and money. The seating on our hex tables has universal access to accommodate a wheelchair. The easy slide in access seating allows for ease of use. They are perfect for office areas there is no stepping over a seat on this table. The 100% recycled plastic lumber construction is assembled with a heavy duty frame of solid 4x4 and 2x4 lumber and all held together using stainless steel fasteners making it durable and maintenance-free. It will not rust, or need paint. The recycled plastic lumber with rich, bold colors molded-in is available for this product in our full spectrum of offered colors which make them a complimentary and attractive application perfect for schools, libraries, churches, parks and local community centers. This item is shipped partially assembled with full instructions for the minimal assembly required to finish the structure using standard hand tools. Our optional anchor kit is available to securely affix the unit in place to aid as a theft deterrent.

#### Product Specifications

#### Product reviews

Weight:	235 lbs
Height:	17.5 in
Length:	40 in
Width:	45.25 in
Picnic Table Type	Picnic Table
Construction	Recycled Plastic
Table Shape	Hexagonal
ADA Compliant	Yes
Mounting Method	Portable
Assembly Required	Yes



### MATERIALS

Thick-walled DOM tubing  
TIG welded to laser-cut steel  
Cut-resistant air hose

Added cabled tools  
are available

### FINISH

#### Powder Coat

Long-lasting, durable red or black powder coated finish.  
17 custom colors are available

### MOUNTING

#### Surface Mount

Bolts to concrete with 3/8" anchors

Note: this unit is to be mounted to concrete only.

### MINIMAL SPACE USE RECOMMENDATION

Note: These setbacks are for the bike pump and work stand when installed together

#### Public Work Stand

Walls or Object Setbacks: Minimum 48"

Parallel Wall Setbacks: Minimum 12"


Perpendicular Street Setbacks: Minimum 60"

Parallel Street Setbacks: Minimum 96"

\*These are our suggested minimal clearances

#### Public Bike Pump

Mount in line with the flange for the Work Stand  
maximum 6" away.





# Halsey Taylor®

[Home Page](#)

*Satisfying Thirsts Since 1912*

● [About Halsey Taylor](#)

● [News!](#)

● [Products](#)

● [Sales](#)

● [Services](#)

● [Request Literature](#)

● [Contact Us](#)

**4880FR-4881FR.jpg**



[Back to Thumbnails](#)

For Customer Service, please call 800.223.5529  
For Technical Service, please call 800.260.6640  
To order Service Parts, please call 800.834.4816

[Legal Notice](#) | [Privacy Statement](#)

© 2000 - 2014 Halsey Taylor





**Halsey Taylor**<sup>®</sup>  
Satisfying Thirsts Since 1912

**MODEL:**   ☐ 4880 FR (30")   ☐ 4881 FR (36")



These fountains are certified to  
NSF/ANSI 61.

#### GENERAL

Pedestal, cast iron closed base with forest green enamel finish for year-round beauty with minimum maintenance. Contour-formed basin with rounded corners and edges reduces splatter, insures proper drainage and prevents standing waste water. **Model 4880FR** is 30" high and **Model 4881FR** is 36" high

#### FREEZE-RESISTANT VALVE SYSTEM

Freeze-resistant valve designed for ground installation 18" below the frost line. 60" of access tubing provided with the freeze-resistant valve system. The length of the tubing can be adjusted in the field for lesser frost depths.

#### BUBBLER

Exclusive one-piece, vandal-resistant, chrome-plated two-stream mound-building bubbler with non-removable anti-squirt feature and integral hood insures a satisfying drink of water.

#### PUSHBUTTON ACTUATION MECHANISM

Self closing, vandal-resistant pushbutton does not require grasping or twisting.

#### AUTOMATIC STREAM HEIGHT REGULATOR

Self-closing assembly is located inside unit to prevent tampering. Unit resists corrosion and liming. A constant stream height is automatically maintained under line pressures that vary from 20 to 105 psi.

#### WATER INLET

3/8" NPT fitting

#### DRAIN OUTLET

Drain requirements are detailed in owner's manual.

#### SUGGESTED SPECIFICATIONS

Fountain shall include pushbutton on the front. Shall include contour-formed basin to eliminate splashing and standing water, and shall have rounded corners and edges. Projector shall be single-stream type with integral hood guard and anti-squirt feature. The manufacturer shall certify the unit to meet the requirements of NSF/ANSI 61, and the Safe Drinking Water Act.

Note: Continued product improvement makes specifications subject to change without notice. See Halsey Taylor website for most current spec sheet.

## Freeze-Resistant Pedestal Fountain



Standard Finish is Forest Green enamel.

Each 4880 and 4881 consists of 2 cartons  
as follows:

Fountain  
Freeze-Resistant Kit

Service stop not included.

Shipping weight: 87 lbs.

JOB NAME: \_\_\_\_\_

ENGINEER/CONTRACTOR NAME: \_\_\_\_\_

APPROVAL: \_\_\_\_\_

DATE: \_\_\_\_\_

[halseytaylor.com](http://halseytaylor.com)

HALSEY TAYLOR, 2222 CAMDEN COURT, OAK BROOK, ILLINOIS 60523



4880 FR (30"), 4881 FR (36")

## Freeze-Resistant Pedestal Fountain

(CONTINUED)

### MOUNTING INSTRUCTIONS and PLUMBING CONNECTIONS



Site and drainage excavation is required for fountain installation. Refer to owner's manual for site preparation details. Provide solid, well-drained surface to mount pedestal fountain (concrete pad recommended). (3) 1/2" anchor bolts (not included) should be attached firmly to mounting surface in order to secure fountain. Refer to rough-in diagram and be sure to allow an opening for the freeze-resistant valve in the ground as shown in the installation instructions that accompany the valve system. Refer to local codes for any additional requirements.

NOTE: Fountain is not furnished with service valve. Assemble fountain to prepared site and mounting pad.

Position pedestal over plumbing and secure base to anchor bolts. Remove access panels and connect supply and water lines. Turn on water supply and check for leaks. Refer to owner's manual for detailed instructions.

### OPERATING PRESSURES:

Supply water- 20 psi minimum to 105 psi maximum.



*Halsey Taylor®*